

**ADDENDUM 4
TO THE CONTRACT PROVISIONS AND CONTRACT PLANS**

FOR

**CITY OF LONG BEACH
REGIONAL BIOSOLIDS FACILITY**

G&O #18522

ISSUED THIS DATE: THURSDAY, APRIL 4, 2019

**BID OPENING: 2:00 PM (LOCAL TIME) ON
TUESDAY, APRIL 9, 2019
CITY OF LONG BEACH
115 BOLSTAD AVENUE WEST
LONG BEACH, WASHINGTON 98631**



Bidder shall acknowledge receipt of this Addendum on Page P-4 of the Proposal.

TO PROSPECTIVE BIDDERS:

The attention of all prospective bidders on the above project is directed to the following additions and modifications to the Contract Provisions and Contract Plans.

I. ADDITIONS, MODIFICATIONS, AND/OR DELETIONS TO THE TECHNICAL SPECIFICATIONS

ITEM 1:

Page 02740-1, Specification Section 02740-2.1, HOT MIX ASPHALT PAVEMENT

Under Subsection A, **REVISE** the first sentence of the first paragraph as shown below (added text is italicized, deleted text is shown as strike out):

“Hot mix asphalt pavement, HMA, CL. 1/2” PG 64-22, shall conform to Sections 5-04.2, *5-04.3(7)*, *5-04.3 (8)*, and 5-04.7 of the WSDOT Standard Specifications.”

ITEM 2:

Page 02740-3, Specification Section 02740-3.2, ASPHALT CONCRETE PAVEMENT PLACEMENT

REVISE the first sentence of the first paragraph as shown below (added text is italicized, deleted text is shown as strike out):

“Asphalt concrete pavement materials shall be placed on compacted subgrade materials, as shown on the Plans, as indicated elsewhere in these Specifications, and in conformance with Sections 5-04.3(1), 5-04.3(2),

5-04.3(3), 5-04.3(4), 5-04.3(5), 5-04.3(9), 5-04.3(10), 5-04.3(11), 5-04.3(12), 5-04.3(13), 5-04.3(14) 5-04.3(16) and 5-04.3(20) of the WSDOT Standard Specifications.”

ITEM 3:

Page 07400-3, Specification Section 07400-2.2 A., Panels

Under Subsection 1., **DELETE** the word “multiwall” from the first sentence.

II. ADDITIONS, MODIFICATIONS, AND/OR DELETIONS TO THE CONTRACT PLANS

ITEM 1:

SHEET GD-2, GENERAL DETAILS

ADD the following notes to the Asphalt Paving Detail:

“NOTES:

1. ASPHALT PAVING SHALL BE PLACED IN TWO LIFTS.
2. PLACE A TACK COAT OF ASPHALT ON THE FIRST LIFT PRIOR TO PLACEMENT OF SUBSEQUENT LIFT.”

ITEM 2:

SHEET S-2, SPECIAL INSTRUCTION SCHEDULE, SUPPLEMENTAL STRUCTURAL APPREVIATIONS, AND STRUCTRUAL LEGEND

On the INSPECTION SCHEDULE NOTES, **DELETE** Note 6 and **REPLACE** with the following:

- “6. ALL TESTING SHALL BE PAID FOR BY THE CONTRACTOR.”